

TOGETHER
WE DELIVER.



MONADELPHOUS ENGINEERING

FLAXBOURNE COMMUNITY IRRIGATION SCHEME

NICK HOUGHTON
19th December 2017

CHRIS EMER

TOGETHER
WE DELIVER.

AGENDA

- Quick Introduction to Monadelphous
- Scheme overview
- Q & A
- Shareholder specific questions

WHO ARE MONADELPHOUS?

- Monadelphous is a leading Australian engineering group
- Providing construction, maintenance and industrial services to the resources, energy and infrastructure sectors.
- 2016/2017 Company turnover was \$1.3Bn
- Our reputation is that “we deliver what we promise”
- The safe way is the only way

TOGETHER
WE DELIVER.

WHO ARE MONADELPHOUS?

- Ashburton Lyndhurst
- Barrhill Chertsey Irrigation Scheme
- Amuri Irrigation Scheme
- Pukaki Irrigation Scheme
- Kurow Duntroon Irrigation Scheme


 Monadelphous
WATER INFRASTRUCTURE

CONCEPT DESIGN

- 233.1 l/s (1,119 ha) extracted from Ure River
- Future expansion of scheme allowed for
- Potential for Winter extraction
- Pipe DN560mm → DN63mm
- 3-4 submersible pumps totaling 500 kW drawing from 25m below surface
- Flowrate based on 1.8mm/day (0.208 l/s/ha)
- 5-6 bar (73-87 PSI) pressure in general

TOGETHER
WE DELIVER.

CONCEPT DESIGN




TOGETHER
WE DELIVER.

PIPELINE MATERIAL


- HDPE from DN560 → DN32
 - 22m lengths
 - Fusion welded on site
- Pipe storage

PIPELINE INSTALL

- 10-30m construction corridor
- 80-300m/day
- 750mm minimum cover



PIPELINE INSTALL




Key Programme Considerations

- Each zone needs to have sufficient plant + resource to meet daily rates.
- Works in each zone need to progress at same speed to meet daily rates.

SCHEME OFFTAKES

- Point of connection to the scheme
- Isolation, air management, flow measurement, pressure management*, telemetry
- <DN80mm typically below ground
- ≥DN80mm typically above ground
- Telemetry feeding into central SCADA system

SCHEME OFFTAKES



TIMEFRAME / PROGRAMME

- 28 Sept 2017 - Monadelphous nominated preferred contractor
- 6th April 2018 - Bore field investigation complete
- 31 May 2018 - Consent granted & Functional Design to begin
- 7th Sept 2018 - Finalize contract price and contract
- 1st Oct 2018 - Mobilize for construction
- Aug 2019 - Summer trial operation commence

**TOGETHER
WE DELIVER.**

QUESTIONS

